

- LIST OF SHEETS**
- FOUNDATION PLAN
  - FIRST FLOOR PLAN
  - SECOND FLOOR PLAN
  - ROOF PLAN
  - FRONT AND LEFT SIDE ELEVATION
  - REAR AND RIGHT SIDE ELEVATION
  - FINISHED LOWER LEVEL PLAN
  - FIRST AND SECOND FLOOR ELECTRIC PLANS
  - SECTIONS & DETAILS
  - BRACING PLANS & DETAILS
  - GENERAL NOTES

**LEGEND**

	WALL FILL / BRICK
	BRG. WALL
	BRG. FROM ABV.
	WALL BRACING
	POST & HEADER
	GIRDER TRUSS
	MTL. HANGER
	POST

**BUILDING CODE INFORMATION:**

CREVE COEUR, MISSOURI

BUILDING: 2021 INTERNATIONAL RESIDENTIAL (BUILDING) CODE

ENERGY: 2015 INTERNATIONAL ENERGY CONSERVATION CODE

PLUMBING: 2015 UNIFORM PLUMBING CODE

MECHANICAL: 2015 INTERNATIONAL MECHANICAL CODE

ELECTRICAL: 2014 NATIONAL ELECTRIC CODE

OTHER: 2021 INTERNATIONAL PROPERTY MAINTENANCE CODE

2021 INTERNATIONAL SWIMMING POOL AND SPA CODE

## FOUNDATION PLAN

1/4" = 1'-0"

OVERALL FOUNDATION PLAN  
CHANGE - WALL THICKNESS  
HAS CHANGED FROM 12"  
THICK TO 10" THICK

## COLUMN PAD SCHEDULE


- FTG-A 30"x30"x12"D. CONCRETE PAD  
W/ #4 BARS @ 8" O.C. EACH WAY
- FTG-B 36"x36"x12"D. CONCRETE PAD  
W/ #4 BARS @ 8" O.C. EACH WAY
- FTG-C 42"x42"x12"D. CONCRETE PAD  
W/ #4 BARS @ 8" O.C. EACH WAY
- FTG-D 48"x48"x12"D. CONCRETE PAD  
W/ #4 BARS @ 8" O.C. EACH WAY

KEEP A SET OF PLANS ON  
JOB SITE FOR INSPECTORS  
REFERENCE UNTIL FINAL  
INSPECTION IS COMPLETE

APPROVED REVISION(S)  
TO BUILDING PERMIT NO. 25-1396  
DATE 9.30.25  
PER   
CITY OF CREVE COEUR




Jim Bulejski Architects  
9820 WARINGTON SQUARE



## BEAM SPLICE DETAIL

3/4" = 1'-0"



## GARAGE FTG. IN RELATION TO BASEMENT FOOTING

1/4" = 1'-0"

## FOUNDATION DRAWING NOTES

- BASEMENT SLAB: 3'-1/2" CONCRETE SLAB OVER 6 MIL. VAPOR BARRIER (LAP JOINTS MIN. 6" AND SEAL) OVER MIN. 4" GRAVEL OR CRUSHED STONE (SLOPE TO FLOOR DRAIN).
- GARAGE SLAB: 4" CONCRETE SLAB WITH 6"x6" W1.4XW1.4 WWF OVER 6 MIL. VAPOR BARRIER (LAP JOINTS MIN. 6" AND SEAL) OVER MIN. 4" GRAVEL OR CRUSHED STONE (SLOPE TO GARAGE DOOR MINIMUM 4" U.N.O.).
- EXTERIOR PORCH/PATIO SLABS: 4" CONCRETE SLAB WITH 6"x6" W1.4XW1.4 WWF OVER MIN. 4" GRAVEL OR CRUSHED STONE. SLOPE AWAY FROM FOUNDATION WITH EDGES TURNED DOWN BELOW GRADE MINIMUM 1/2" OR TO TOP OF FOUNDATION WALL.
- (2) #4 BARS TOP, MIDDLE, AND BOTTOM, 24" EA. WAY. TYP. AT ALL INTERSECTING WALLS.
- #4 BARS AT 24" O.C. DOWEL INTO FOUNDATION WALL AND BEND 24" INTO CONCRETE SLAB. TYPICAL AT EXTERIOR PORCH SLABS AND GARAGE SLAB (ADJACENT TO BASEMENT FOUNDATION WALL).
- HOLD DOWN TOP OF FOUNDATION WALL AT DOOR TO RECEIVE CONCRETE SLAB.
- FOOTINGS AND PIERS: BOTTOM OF FOOTINGS TO BE MINIMUM 30" BELOW GRADE. PIERS TO EXTEND MIN. 24" INTO SOLID, UNDISTURBED SOIL AND MIN. 30" BELOW GRADE.
- DRAINAGE SYSTEM SHALL DISCHARGE BY GRAVITY TO DAYLIGHT OR BE CONNECTED TO AN APPROVED SUMP (MIN. 24" IN DIAMETER OR 20 INCHES SQUARE AND SHALL EXTEND MIN. 24 INCHES BELOW THE BOTTOM OF THE BASEMENT FLOOR. SUMP SHALL HAVE A FITTED COVER. PROVIDE PUMP IF DRAINAGE SYSTEM IS CONNECTED TO SUMP PIT. DISCHARGING TO OR WITHIN 10' OF A SIDEWALK, DRIVEWAY, STREET, PROPERTY LINE, OR TO CREATE A NUISANCE TO ADJOINING PROPERTIES IS PROHIBITED.
- CLASS "B" U.L. APPROVED HVAC FLUE (SIZED BY HVAC CONTRACTOR) AT GAS FURNACE AND WATER HEATER. PROVIDE MINIMUM 2" CLEARANCE.
- ELECTRICAL PANEL: (200 AMP. MINIMUM / 600 AMP. MAXIMUM) TO BE SIZED AND LOCATED BY ELECTRICAL CONTRACTOR.
- STEEL COLUMNS SHALL BE SCHEDULE 40, SIZED PER PLAN. ALL COLUMNS SHALL HAVE A CAP AND BASE. ADJUSTABLE COLUMNS PERMITTED UNLESS NOTED TO BE FIXED.
- MINIMUM OF (2) #5 REINFORCING BARS SHALL BE PROVIDED AROUND ALL WINDOW AND DOOR OPENINGS IN PLAIN CONCRETE FOUNDATION AND BASEMENT WALLS. BARS SHALL EXTEND A MINIMUM OF 24" BEYOND THE CORNERS OF THE OPENINGS.
- CONTRACTOR SHALL NOT BACKFILL UNTIL CONCRETE FOUNDATION HAS CURED FOR A MINIMUM OF 7 DAYS. INSTALL BRACES @ 12'-0" O.C. AND/OR WITHIN 12'-0" OF FOUNDATION WALL CORNERS. DO NOT BACKFILL UNTIL COMPLETION OF FIRST FLOOR FRAMING. DO NOT REMOVE TEMPORARY BRACING UNTIL COMPLETION OF BACKFILLING.
- UNFINISHED BASEMENTS SHALL BE INSULATED TO MIN. R-10. SEE GENERAL NOTES AND DETAILS.

MECHANICAL: GAS APPLIANCES LOCATED IN SPACES WHERE THE VOLUME IS LESS THAN 50 CUBIC FEET PER 1,000 BTU/HR. INPUT RATING. SHALL HAVE COMBUSTION AIR PROVIDED. MECHANICAL CONTRACTOR SHALL CALCULATE, SPECIFY, AND COORDINATE WITH G.C. ALL ADDITIONAL COMBUSTION AIR AS REQUIRED BY THE MECHANICAL CODE AND LOCAL JURISDICTIONS. LOUVERED DOORS SHALL BE PERMITTED BY THE ARCHITECT IF CALLED OUT ON THE PLANS (VERIFY WITH OWNER). IF ADDITIONAL COMBUSTION AIR IS REQUIRED, MECHANICAL CONTRACTOR SHALL PROVIDE THE FOLLOWING:  
USING INSIDE AIR: PROVIDE 1 SQ. IN. PER 1000BTU/HR. IN HIGH AND LOW OPENINGS. MINIMUM OPENING SIZE 100 SQ. IN.  
USING OUTSIDE AIR: PROVIDE 1 SQ. IN. PER 4,000 BTU/HR. (1 SQ. IN. PER 2,000 BTU/HR. IF DUCTED HORIZONTAL OPENING).

HIGH CEILINGS ARE IMPORTANT TO THE OWNER. COORDINATE DUCTWORK ARRANGEMENTS WITH OWNER BEFORE INSTALLING. RUN DRYWALL DIRECTLY BELOW STEEL BEAM AND DO NOT DROP DOWN LOWER THAN THIS POINT.

PLUMBING CONTRACTOR TO LOCATE PLUMBING PIPING AND PLUMBING STACKS TO AVOID CONFLICT WITH FINISH BASEMENT PLAN AND TO AVOID CONFLICT WITH FUTURE FINISH WORK THAT MAY OCCUR IN UNFINISHED BASEMENT AREAS. REVIEW LOCATION OF PLUMBING STACKS WITH OWNER.

date: 4/23/2025  
PERMIT: 7/11/2025  
CITY COMMENTS: 8/15/2025  
REVISIONS: 9/29/2025

JIM BULEJSKI ARCHITECTS  
315 MARSHALL AVE. SUITE 100 ST. LOUIS, MO 63119  
PHONE: 314-662-6700 • FAX: 314-662-6702  
E-MAIL: KATE@BARCHITECT.COM

STATE OF MISSOURI  
KATHARINE S. NIESSEN COOK  
NUMBER A-2024034183

Douglas Properties



9820 Warington Square  
Creve Coeur, MO 63141

NEW RESIDENCE AT:

FOUNDATION PLAN

sheet: 1 of 11










### FIRST FLOOR PLAN

1/4" = 1'-0"

2546 S.F.

2546 S.F. 1ST FLR  
1361 S.F. 2ND FLR  
3897 S.F. TOTAL



- #### FLOOR PLAN DRAWING NOTES
- ALL INTERIOR WALLS TO BE 3 1/2" (2X4 STUDS), UNLESS NOTED OTHERWISE (U.N.O.). ALL INTERIOR DIMENSIONS ARE TO FACE OF STUD. ALL EXTERIOR DIMENSIONS ARE TO FACE OF SHEATHING (U.N.O.).
  - POST INDICATED SHALL BE MINIMUM (2) 2X WALL THICKNESS, GLUED AND NAILED, UNLESS NOTED OTHERWISE. EXCEPT: POSTS CARRYING MINIMAL LOADS, LESS THAN 8'-0" IN HEIGHT AND SUPPORTING HEADERS SPANNING 3'-0" OR LESS MAY CONSIST OF A SINGLE 2X CRIPPLE AND (1) FULL HT. UNBROKEN STUD UNLESS NOTED OTHERWISE. MINIMUM HEADER SIZE (2) 2X10'S GLUED AND NAILED.
  - MINIMUM HEADER SIZE 2-2X10'S GLUED AND NAILED, U.N.O.
  - FIREPLACE: HEATILATOR CALIBER CD4236 (36" VIEWING AREA) OR CD4842 (42" VIEWING AREA) DIRECT VENT GAS PER FABRICATED FIREPLACE OR AS SELECTED BY OWNER (SEE SECTION). SURROUND, MANTLE, AND HEARTH TO BE SELECTED BY OWNER. COORD. WITH MFR. FOR MIN. ROUGH-IN DIMENSIONS, HEARTH WIDTH, AND EXTENSION.
  - PROVIDE 2" MINIMUM CLEARANCE TO COMBUSTIBLES AT ALL GAS FLUES, TYPICAL.
  - GARAGE/HOUSE SEPARATION WALL TO BE INSULATED MINIMUM R-13.
  - GARAGE-ATTACHED: 1/2" DRYWALL ON GARAGE SIDE OF GARAGE/HOUSE SEPARATION WALL UP TO 5'8" TYPE X DRYWALL CEILING.
  - DRYWALL ALL EXTERIOR GARAGE WALLS, TYP. (INSULATION OPTIONAL)
  - COOKTOP WITH EXHAUST HOOD. PROVIDE GAS AND/OR ELECTRIC HOOKUPS AS REQUIRED. IF EXHAUST EXCEEDS 400 C.F.M. (ST. LOUIS COUNTY / LAJUE: 600 C.F.M.), PROVIDE MAKE-UP AIR. IF IN ST. LOUIS COUNTY, MECHANICAL CONTRACTOR TO SUBMIT DESIGN FOR REVIEW. ALL EXHAUST TO BE VENTED TO EXTERIOR PER ALL LOCAL CODES.
  - LAUNDRY: WASHER TO BE PLACED IN A FLOOR SAVER WITH DRAIN. PROVIDE IN-WALL WASHER OUTLET BOX AND RECESSED DRYER VENT BOX. DRYER TO VENT TO EXTERIOR.
  - SEE ELECTRIC SHEET FOR DEVICE LOCATIONS.
  - INTERIOR DOOR TRIM: 4 1/4" CASING WITH 4 3/4" PLINTHS. PROVIDE MIN. 5 1/2" (7" PREFERRED) FROM PERPENDICULAR FRAME WALL TO FINISH DOOR OPENING. TYP. U.N.O.

date: 4/23/2025  
PERMIT: 7/11/2025  
CITY COMMENTS: 8/15/2025  
REVISIONS: 9/29/2025

JIM BULEJSKI  
ARCHITECTS

STATE OF MISSOURI  
KATHARINE S. NIESSEN COOK  
NUMBER A-2024034183

NEW RESIDENCE AT:

9820 Warington Square  
Creve Coeur, MO 63141

FIRST FLOOR PLAN


2 of 11



4/23/2025

7/11/2025



REVISIONS:



## SECOND FLOOR PLAN

$$1/4" = 1'-0"$$

1351 S.F.



**4-STUD CORNER**

STUD CORNER GROUPS SHALL NOT CREATE ANY CONCEALED AIR SPACES THAT CANNOT BE INSULATED FROM THE INTERIOR. "CALIFORNIA CORNER" SHOWN

### 3-STUD CORNER

# TYP. CORNER

SCALE 3/4" = 1'-0"

FRAMING —  
TYP. INSULATION —

FRAMING ———  
TYP. INSULATION  
SEE GEN. NOTES

1X4 MOLDING NAILED TO SOLID FRAMING.  
(USE 2X4 STOCK AT GARAGE SCUTTLE)

DTL @ ATTIC

DTL @ ATTIC

DTL. @ ATTIC

20415-248 41.0%

SCALE 3/4" = 1'-0"

TYP. EXTERIOR WALL CONSTRUCTION  
 HEADER - SEE PLAN  
 MIN. 1/2" FOAMBOARD INSULATION  
 BLOCKING AS REQUIRED

BLOCKING AS REQ'D

© 2006 The Authors  
Journal compilation © 2006 Blackwell Publishing Ltd

TYP EXTERIOR

## III. EXTERIOR

# WALL HEADER

Source: U.S. Census Bureau, *U.S. Census of Population, Housing, and Agriculture*, 1990, 2000, and 2010.

SCALE 3/4" = 1'-0"

## NOTES

SECOND FLR. FURNACE SHALL BE SET IN OVERFLOW DRAIN PAN. PROVIDE SOUND BATTS AROUND & IN FLOOR BELOW FURN. ROOM. INSTALL 1/2" HOMISOTE SOUND BRD. UNDER DW AND WEATHER STRIP DR FOR SOUND CONTROL. MECH. CONTRACTOR TO SUPPLY COMBUSTION AIR. (NO LOUVER

DUCTS TO BE INSULATED TO A MIN. R-8.

ENERGY CONSERVATION REQUIRED WITH COMBUSTION / VENTILATION

OUTSIDE AIR:

- SOLID, SELF-CLOSING WEATHERSTRIPPED DOOR
- R-13 INSULATION AT INTERIOR WALLS


- R-19 INSULATION AT FLOOR/CEILING

- WRAPPED, INSULATED DUCTS
- STOPPED WALL PENETRATIONS

## FLOOR PLAN DRAWING NOTES


1. ALL INTERIOR WALLS TO BE 3/12 (TWO FIVE EIGHTS), UNLESS NOTED OTHERWISE (10.0 U.I.). ALL INTERIOR WALLS TO BE 2X4 STUDS. ALL EXTERIOR DIMENSIONS ARE TO FACE OF SHEATHING (U.O.I.).
2. POST INDICATED SHALL BE MINIMUM (2) 2X WALL THICKNESS, GLUED AND NAILED, UNLESS NOTED OTHERWISE. EXCEPTION: POSTS CARRYING MINIMAL LOADS, LESS THAN 8'-0" IN HEIGHT AND SUPPORTING HEADERS SPANNING 3'-0" OR LESS MAY CONSIST OF A SINGLE 2X4 HEAD AND (1) FULLY BRACED STUD. WHEN STUDS ARE USED, THEY SHALL BE MINIMUM 1/2" HEAD SIZE AND (2) FULLY GLUED AND NAILED.
3. MINIMUM HEADER SIZE 2-X2X10S GLUED AND NAILED, U.O.I.
4. FIREPLACE: HEATILATOR CALIBER C4236 (36" VIEWING AREA) OR C42842 (42" VIEWING AREA) DIRECT VENT GAS PRE-FABRICATED FIREPLACE OR AS SELECTED BY OWNER (SEE SECTION). SURROUND, MANTLE, AND HEARTH TO BE SELECTED BY OWNER. COORD. WITH OWNER FOR MIN. CLEARANCE TO COMBUSTIBLES AT ALL GAS FIRES, TYPICAL.
5. PROVIDE 2" MINIMUM CLEARANCE TO COMBUSTIBLES AT ALL GAS FIRES, TYPICAL.
6. GARAGE/HOUSE SEPARATION WALL TO BE INSULATED MINIMUM R-13.
7. GARAGE-ATTACHED 1/2" DRYWALL ON GARAGE SIDE OF GARAGE/HOUSE SEPARATION WALL UP TO 5'-8" TYPE X DRYWALL CEILING.
8. DRYWALL ALL EXTERIOR GARAGE WALLS, TYPE (INSULATION OPTIONAL).
9. CO-OP WORK WITH EXHAUST FAN, RANGE HOOD AND/OR ELECTRIC HOODS (IF REQUIRED). IF EXHAUST EXCEEDS 400 C.F.M. (ST. LOUIS COUNTY / LADUE: 600 C.F.M.), PROVIDE MAKE-UP AIR. IF IN ST. LOUIS COUNTY, MECHANICAL CONTRACTOR TO SUBMIT DESIGN FOR REVIEW. ALL EXHAUST TO BE EXTENDED TO EXTERIOR PER ALL LOCAL CODES.
10. LAUNDRY: WASHER TO BE PLACED IN A FLOOR SINK BATH. PROVIDE IN-WALL LAUNDRY OUTLET BOX AND RECESSED DRYER VENT BOX. DRYER TO VENT TO EXTERIOR.
11. INTERIOR DOOR THRESHOLD TO BE 1/2" THICK.
12. INTERIOR DOOR TRIM 4 1/4" CASING WITH 3/4" PLINTH. PROVIDE MIN. 5 1/2" (IF PREFERRED) FROM PERPENDICULAR FRAME WALL TO FINISH DOOR OPENING. TYPE 1/2"






**FIREPLACE ELEVATION**

3/8" = 1'-0"




**STAIR SECTION**

3/8" = 1'-0"



**LEDGER @ GARAGE**

3/4" = 1'-0"



**ROOF / FRAMING PLAN**

1/4" = 1'-0"

**ROOF FRAMING NOTES**

- POST INDICATED SHALL BE MINIMUM (2) 2X WALL THICKNESS, GLUED AND NAILED, UNLESS NOTED OTHERWISE. MINIMUM HEADER SIZE (2) 2X10'S. GLUE AND NAIL ALL MULTIPLE BEAM MEMBERS.
- EXCEPTION: POSTS CARRYING ROOF LOADS ONLY AND NOT EXCEEDING 8'-1" IN HEIGHT AND SUPPORTING HEADERS SPANNING 3'-0" OR LESS MAY CONSIST OF A SINGLE 2X CRIPPLE AND (1) FULL HT. UNBROKEN STUD UNLESS NOTED OTHERWISE.
- SEE FIRST AND SECOND FLOOR PLANS FOR INTERIOR CEILING CONDITIONS.
- TRUSS LAYOUT SHOWN IS FOR DIAGNOSTIC PURPOSES ONLY. SEE MANUFACTURER'S SHOP DRAWINGS FOR ACTUAL LAYOUT.
- TRUSSES (AT 8:12 SLOPE) TO HAVE 8" HEEL HEIGHT UNLESS NOTED OTHERWISE.

date: 4/23/2025  
PERMIT: 7/11/2025  
CITY COMMENTS: 8/15/2025  
REVISIONS: 9/29/2025

**JIM BULEJSKI ARCHITECTS**  
315 MARSHALL AVE - SUITE 100 - ST. LOUIS, MO 63119  
PHONE: 314-462-6700 • FAX: 314-462-6702 •  
E-MAIL: KATE@BARCHITECT.COM •

**KATHARINE S. NIESSEN COOK**  
NUMBER A-2024034183

**Douglas Properties**


**NEW RESIDENCE AT:**

**9820 Warington Square**  
**Creve Coeur, MO 63141**

**ROOF / FRAMING PLAN**

sheet: **4** of 11






LEFT SIDE ELEVATION

1/4" = 1'-0"

TYPICAL LAP SIDING:  
JAMES HARDIE® FIBER CEMENT BOARD  
SIDING AND TRIM. (TYP.)  
SMOOTH 6" EXPOSURE HARDIE PLANK  
SIDING (TYP.)

PREFINISHED COLOR TAUPE OR PRIMED  
FOR FIELD PAINT. ALL TRIM TO BE  
PREFINISHED SAME AS SIDING.

TYPICAL BOARD & BATTEN SIDING:  
5/4"x6" TRIM BRDS OVER 7/16"  
FIBER-CEMENT SIDING (HARDIE  
PANEL)




FRONT ELEVATION

1/4" = 1'-0"

SECTION @ GARAGE BAY

SCALE 3/4" = 1'-0"



SECTION @ GABLE END

3/4" = 1'-0"

ELEVATION DRAWING NOTES

- SLOPE GRADE AWAY FROM FOUNDATION MINIMUM 1"FT. FOR A DISTANCE OF 8'-0" OR TO A SWALE.
- FOOTINGS AND PIERS: BOTTOM OF ALL FOOTINGS TO SET ON SOLID, UNDISTURBED SOIL. PIERS TO EXTEND MINIMUM 24" INTO SOLID, UNDISTURBED SOIL. BOTH SHALL BE MINIMUM 30" BELOW GRADE.
- DECK DOORS: SECURELY BARRICADE DOOR UNTIL DECK IS BUILT AND APPROVED.
- ROOF FLASHING: PROVIDE CORROSION-RESISTANT METAL FLASHING AT ALL ROOF VALLEYS, WALL AND CHIMNEY INTERSECTIONS, PORCHES, DECK, ETC. ROLLED ROOFING OR (2) LAYERS OF TYPE 1 UNDERLAYMENT MAY BE SUBSTITUTED FOR FLASHING AT THE ROOF VALLEY PROVIDED THE SHINGLES ARE INTERLACED.
- GENERAL CONTRACTOR SHALL CONFIRM USE OF ALL TRIM ACCESSORIES AND MODEL NUMBERS WITH SUPPLIER BEFORE ORDERING.
- WINDOW SIZES ARE GENERIC. WINDOW TYPE: ALUMINUM CLAD EXTERIOR, WOOD INTERIOR. INTERIOR: PRIMED/STAINED. EXTERIOR: BLACK/WHITE.
- EGRESS WINDOW REQUIREMENTS:  
(COMPLY WITH IRC 2015 SECTION R310)
  - 44" MAX. SILL HT. A.F.F. AT BASEMENT WINDOWS
  - MIN. NET CLEAR OPENING OF 5.7 S.F. (6 S.F. ALLOWED AT GRADE FLOOR OPENINGS)
  - MIN. OPENING HEIGHT = 24" NET CLEAR
  - MIN. OPENING WIDTH = 20" NET CLEARCONTRACTOR SHALL SUBMIT MANUFACTURER'S DATA WITH PERMIT DOCUMENTS TO SHOW THAT EGRESS WINDOWS MEET THESE REQUIREMENTS.
- WINDOW OPENING REQUIREMENTS:  
(COMPLY WITH IRC 2015 SECTION R312)
  - FOR WINDOWS WITH SILLS LESS THAN 24" ABOVE THE FLOOR AND MORE THAN 72" ABOVE GRADE, LIMIT WINDOW OPENINGS TO PROHIBIT PASSAGE OF 4" SPHERE.
  - PROVIDE MECHANISM TO ALLOW FOR EMERGENCY ESCAPE.
  - MECHANISM TO AUTOMATICALLY RESET AFTER BEING DISABLED.

date: 4/23/2025  
PERMIT: 7/11/2025  
CITY COMMENTS: 8/15/2025  
REVISIONS: 9/29/2025

JIM BULEJSKI  
ARCHITECTS

345 MARSHALL AVE. SUITE 100 ST. LOUIS, MO 63119  
PHONE: 314-862-8700 • FAX: 314-862-8702  
E-MAIL: KATE@JBARCHITECT.COM

STATE OF MISSOURI  
KATHARINE S. NIESEN COOK  
NUMBER A-2024034183

Douglas  
Properties

NEW RESIDENCE AT:

9820 Warington Square  
Creve Coeur, MO 63141



FRONT AND LEFT ELEVATIONS

sheet: 5 of 11










FINISHED LOWER LEVEL PLAN

1/4" = 1'-0"

1309 S.F. FINISHED LOWER LEVEL


NOTE: HIGH CEILINGS ARE IMPORTANT TO THE OWNER  
COORDINATE ALL SOFFITS AND DUCTWORK  
ARRANGEMENTS WITH OWNER BEFORE  
INSTALLING. RUN DRYWALL DIRECTLY BELOW  
STEEL BEAM AND DO NOT DROP DOWN LOWER  
THAN THIS POINT.

ENERGY CONSERVATION REQUIRED WITH COMBUSTION /  
VENTILATION OUTSIDE AIR:  
- SOLID, SELF-CLOSING WEATHER-STRIPPED DOOR  
- R-13 INSULATION AT INTERIOR WALLS  
- R-19 INSULATION AT FLOOR/CEILING  
- WRAPPED, INSULATED DUCTS  
- STOPPED WALL PENETRATIONS



DRAFTSTOPPING DTL.


1 1/2" = 1'-0"



BSMT. WALL SECTION -  
DROPPED CLG.

3/4" = 1'-0"

SEE TYP. WALL SECTIONS FOR  
ADDITIONAL INFORMATION



BSMT. WALL SECTION

3/4" = 1'-0"

SEE TYP. WALL SECTIONS FOR  
ADDITIONAL INFORMATION

FINISHED LOWER LEVEL DRAWING NOTES

- ALL INTERIOR WALLS TO BE 3 1/2" (2X4 STUDS), UNLESS NOTED OTHERWISE (UNO). (OPTIONAL LIGHT GAGE STEEL STUDS) USE PRESSURE TREATED SILL PLATES OR STEEL TRACKS.
- DRAFTSTOPPING: CEILINGS SUSPENDED BELOW WOOD JOISTS OR ATTACHED DIRECTLY TO WOOD FLOOR TRUSSES SHALL BE DRAFT STOPPED AT MAXIMUM 1000 S.F. INTERVALS PARALLEL TO MAIN FRAMING MEMBERS. SEE DETAIL THIS SHEET.
- CEILING HEIGHTS TO BE DETERMINED BY EXTENT OF DUCTWORK, STEEL BEAMS, ETC. (7'-0" MIN. CEILING HEIGHT)
- FURR DOWN CEILING, IF REQUIRED, TO CLEAR BEAMS, DUCTWORK, WIRES, PIPES, ETC., UNLESS NOTE OTHERWISE.
- SET ALL CEILING AS HIGH AS POSSIBLE. PROVIDE ACCESS PANELS TO UTILITIES, CLEANOUTS ETC. IN FINISHED AREAS. VERIFY METHOD WITH OWNER.
- MAINTAIN REQUIRED CLEARANCES AROUND FURNACES AND WATER HEATERS.
- VENT BATHROOM EXHAUST FAN TO EXTERIOR.
- ADJUST LOCATIONS OF RECESSED LIGHT FIXTURES IF REQUIRED FOR FRAMING MEMBERS, DUCTWORK, ETC. REVIEW ALTERNATE LOCATIONS WITH OWNER.

MECHANICAL: GAS APPLIANCES LOCATED IN SPACES WHERE THE VOLUME IS LESS THAN 50 CUBIC FEET PER 1,000 BTU/HR. INPUT RATING. SHALL HAVE COMBUSTION AIR PROVIDED. MECHANICAL CONTRACTOR SHALL CALCULATE, SPECIFY AND COORDINATE WITH GC ALL ADDITIONAL COMBUSTION AIR AS REQUIRED BY THE MECHANICAL CODE AND LOCAL JURISDICTIONS. LOUVERED DOORS SHALL BE PERMITTED BY THE ARCHITECT IF CALLED OUT ON THE PLANS. VERIFY WITH OWNER. IF ADDITIONAL COMBUSTION AIR IS REQUIRED MC SHALL PROVIDE THE FOLLOWING:  
USING INSIDE AIR: PROVIDE 1 SQ. IN. PER 1000BTU/HR. IN HIGH AND LOW OPENINGS. MIN. OPENING SIZE 100 SQ. IN.  
USING OUTSIDE AIR: PROVIDE 1 SQ. IN. PER 4,000 BTU/HR. (1 SQ. IN. PER 2,000 BTU/HR. IF DUCTED HORIZONTAL OPENING)

VENTILATION: UNFINISHED BASEMENTS AND UTILITY ROOMS REQUIRE VENTILATION IN THE AMOUNT OF .05 CFM/SQ.FT. OF AREA. NATURAL VENTILATION (NET OPERABLE AREA) MAY BE SUBSTITUTED AT THE RATIO OF 1% OF THE FLOOR AREA SERVED.

ENERGY CONSERVATION REQUIRED WITH COMBUSTION / VENTILATION OUTSIDE AIR:  
- SOLID, SELF-CLOSING WEATHER-STRIPPED DOOR  
- R-13 INSULATION AT INTERIOR WALLS  
- R-19 INSULATION AT FLOOR/CEILING  
- WRAPPED, INSULATED DUCTS  
- STOPPED WALL PENETRATIONS

date:  
4/23/2025  
PERMIT:  
7/11/2025  
CITY COMMENTS:  
8/15/2025  
REVISIONS:  
9/29/2025

JIM BULEJSKI  
ARCHITECTS

245 MARSHALL AVE. SUITE 100 ST. LOUIS, MO 63119  
PHONE: 314-462-6700 • FACSIMILE: 314-462-6702 •  
E-MAIL: KATE@JBARCHITECT.COM •

STATE OF MISSOURI  
KATHARINE S. NIESSEN COOK  
NUMBER  
A-2024031813

ARCHITECT

NEW RESIDENCE AT:

Douglas  
Properties

9820 Warington Square  
Creve Coeur, MO 63141

FINISHED LOWER LEVEL PLAN


7

of 11




ELECTRICAL SYMBOLS			
DUPLEX OUTLET	WP/ GFI	UNDER CAB. INCANDESCENT	CLICK STRIP
WATER PROOF (WP)			
GROUND FAULT INTERRUPTER (GFI)			
FOURPLEX		BRACKET MOUNT	
SPECIALTY OUTLET	240 V.	CEILING MOUNT	
PHONE			
SWITCH		RECESSED CAN LIGHT	
DIMMER (D)			
CABLE TV OUTLET		RECESSED WALL WASH	
EXHAUST FAN/ MOTOR		FLUORESCENT LIGHT	
COMPUTER NETWORK PORT/ INTERNET ACCESS LINE		FLOOD LIGHT	
	FAN/ LIGHT	PULL CHAIN LIGHT	
CEILING FAN W/ LIGHT		SMOKE DETECTOR	
		CARBON MONOXIDE DETECTOR	

- ELECTRIC PLAN DRAWING NOTES
- NOTE: HOME RUN ALL RG6 AND CAT. 6 TO ONE SPOT IN BSMT. AND LABEL. PROVIDE ROUGH-IN FOR FUTURE DSS.
  - COMPUTER NETWORK PORT TO RECEIVE THE FOLLOWING: (1) RG6 COAX CABLE, (2) CAT. 6 FOR PHONE/INTERNET ACCESS, MODEM, AND NETWORK



ELECTRIC  
SECOND FLOOR PLAN

1/4" = 1'-0"



ELECTRIC  
FIRST FLOOR PLAN

1/4" = 1'-0"

date:  
4/23/2025  
PERMIT:  
7/11/2025  
CITY COMMENTS:  
8/15/2025  
REVISIONS:  
9/29/2025

JIM BULEJSKI  
ARCHITECTS  
345 MARSHALL AVE. SUITE 100 ST. LOUIS, MO 63119  
PHONE: 314-462-8700 • FAX: 314-462-8702  
E-MAIL: KATE@BARCHITECT.COM
















STATE OF MISSOURI  
KATHARINE S. NIESEN COOK  
NUMBER  
A-2024034183

NEW RESIDENCE AT:  
Douglas Properties  
9820 Warington Square  
Creve Coeur, MO 63141

FIRST FLOOR ELECTRIC PLAN  
SECOND FLOOR ELECTRIC PLAN

sheet:  
8  
of 11





date: 4/23/2025  
PERMIT: 7/11/2025  
CITY COMMENTS: 8/15/2025  
REVISIONS: 9/29/2025

JIM BULEJSKI  
ARCHITECTS  
345 MARSHALL AVE - SUITE 100 - ST. LOUIS, MO 63119  
PHONE: 314-662-6700 • FAX: 314-662-6702  
E-MAIL: KATE@JBARCHITECT.COM

KATHARINE S. NIESEN COOK  
NUMBER A-2024034183

Douglas Properties  
9820 Warington Square  
Creve Coeur, MO 63141

NEW RESIDENCE AT:


SECTIONS & DETAILS

sheet:

9


of 11






**METHOD GB PERPENDICULAR  
W/ TRUSS AND JOIST**

8




**METHOD GB W/O TRUSS AND  
JOIST OFFSET ABOVE AND BELOW**

7




**METHOD GB W/ TRUSS AND JOIST  
DIRECTLY ABOVE AND BELOW**


6



**SECOND FLOOR BRACING PLAN**



**OVER RAISED WOOD FLOOR OR SECOND FLOOR -  
FRAMING ANCHOR OPTION (DETAIL 3 OF 3)**



**OVER RAISED WOOD FLOOR OR SECOND FLOOR -  
STRUCTURAL PANEL OVERLAP OPTION (DETAIL 2 OF 3)**


**BRACED WALL PANEL NOTES**

- NEW CONSTRUCTION TO BE BRACED USING CONTINUOUS SHEATHING AS PRESCRIBED IN IRC2015 R602.10.3. CONTINUOUS SHEATHING METHODS REQUIRE STRUCTURAL PANEL SHEATHING TO BE USED ON ALL SHEATHABLE SURFACES ON ONE SIDE OF A BRACED WALL LINE INCLUDING AREAS ABOVE AND BELOW OPENINGS AND GABLE END WALLS. BRACED WALL PANELS SHALL BE CONSTRUCTED IN ACCORDANCE WITH ONE OF THE METHODS IN TABLE R602.10.4.1.
  - BRACED WALL PANELS ALONG A BRACED WALL LINE WITH CONTINUOUS SHEATHING SHALL BE FULL-HEIGHT WITH A LENGTH BASED ON THE ADJACENT CLEAR OPENING HEIGHT IN ACCORDANCE WITH TABLE R602.10.4.2 AND FIGURE R602.10.4.2.
  - BRACED WALL PANELS SHALL BE LOCATED AT THE END OF A BRACED WALL LINE WITH CONTINUOUS SHEATHING AND AT LEAST EVERY 25 FEET ON CENTER. A MINIMUM 24-INCH WOOD STRUCTURAL PANEL CORNER RETURN SHALL BE PROVIDED AT BOTH ENDS OF A BRACED WALL LINE WITH CONTINUOUS SHEATHING IN ACCORDANCE WITH FIG. R602.10.4.4(1) AND FIG. R602.10.4.4(2). SEE DETAILS 1/10 AND 2/10. IN LIEU OF THE CORNER RETURN, A HOLD-DOWN DEVICE WITH A MINIMUM UPLIFT DESIGN VALUE OF 800 POUNDS SHALL BE FASTENED TO THE CORNER STUD AND TO THE FOUNDATION OR FRAMING BELOW IN ACCORDANCE WITH FIG. R602.10.4.4(3).
- METHOD CS-WSP: EXTERIOR WALLS INDICATED AS BWP-METHOD CS-WSP TO HAVE WOOD STRUCTURAL PANELS TO CONFORM TO DOC P5.1 OR DOC P5.2. ALL PANELS SHALL BE IDENTIFIED BY A GRADE MARK OR CERTIFICATE OF INSPECTION ISSUED BY AN APPROVED AGENCY. THE MAXIMUM ALLOWABLE SPANS FOR WOOD STRUCTURAL PANEL WALL SHEATHING SHALL NOT EXCEED THE VALUES IN TABLE R602.3(3). WOOD STRUCTURAL PANEL WALL SHEATHING SHALL BE ATTACHED TO FRAMING IN ACCORDANCE WITH TABLE R602.3(1) OR TABLE R602.3(3). WOOD STRUCTURAL PANELS MARKED EXPOSURE 1 OR EXTERIOR ARE CONSIDERED WATER-REPELLENT SHEATHING UNDER 2015 IRC. THE MINIMUM THICKNESS FOR SHEATHING IS 3/8". PANELS TO BE CONNECTED WITH 6d COMMON NAILS AT 6" SPACING (PANEL EDGE) AND 12" SPACING (INTERMEDIATE SUPPORTS) OR 16 GA. X 1 3/4" STAPLES AT 3" SPACING (PANEL EDGES) AND 6" SPACING (INTERMEDIATE SUPPORTS). THE CONTRACTOR SHALL NOTIFY THE ARCHITECT IF ALTERNATE METHODS ARE DESIRED TO BE EMPLOYED. AS ADDITIONAL CALCULATIONS AND DELINEATION ON THE CONSTRUCTION DOCUMENTS WILL BE REQUIRED. STRUCTURAL ENGINEERING BY OUTSIDE CONSULTANTS MAY BE REQUIRED. THE CONTRACTOR SHALL CONFIRM AND NOTIFY THE ARCHITECT IN WRITING OF THE SUBJECT PROPERTIES SEISMIC DESIGN CATEGORY, IF A 'D' CATEGORY, BEFORE PROCEEDING WITH THE WORK.
- METHOD GB: INTERIOR WALLS INDICATED AS BWP-METHOD GB TO HAVE 1/2" MIN. GWB. BRACING LENGTHS FOR METHOD GB ARE BASED ON THE APPLICATION OF GYPSUM BOARD ON BOTH FACES OF A BRACED WALL PANEL. WHEN METHOD GB IS PROVIDED ON ONLY ONE SIDE OF THE WALL, THE REQUIRED BRACING AMOUNTS SHALL BE DOUBLED. WALL PANELS TO BE CONNECTED WITH NAILS OR SCREWS AT 7" SPACING AT PANEL EDGES INCLUDING TOP AND BOTTOM PLATES; FOR ALL BRACED WALL PANEL LOCATIONS FOR EXTERIOR SHEATHING NAIL OR SCREW SIZE, SEE TABLE R602.3(1). FOR INTERIOR GYPSUM BOARD NAIL OR SCREW SIZE, SEE TABLE R702.3.5. A CLG. OR FLR. JST./TRUSS LOCATED DIRECTLY ABV. AN INTERIOR BRACED WALL LINE SHALL BE ATTACHED WITH 8d NAILS AT 6" O.C. TOENAILED, WHERE THE CLG. OR FLR. JST./TRUSS IS NOT LOCATED DIRECTLY ABV. THE INTERIOR BRACED WALL LINE IS PERPENDICULAR TO THE WALL. ADD 2X4 BLOCKING AT 16" O.C. BETWEEN THE FLR. ROOF FRAMING. THE BLOCKING SHALL BE ATTACHED TO THE FLR./ROOF FRAMING W/ 3-8d NAILS TOENAILED AT EA. END OF THE BLOCK. EA. BLOCK SHALL BE TOENAILED TO THE INTERIOR BRACED WALL PANEL W/ 3-8d NAILS TOENAILED. PROVIDE 2X HORIZONTAL BLOCKING AT ALL HORIZONTAL DRYWALL JOINTS IN BRACED WALL PANELS ONLY (ENTIRE WALL LINE NOT REQUIRED TO BE BLOCKED). SEE DETAILS 6, 7 & 8, SHT. 10.
- METHOD CS-PF: CONTINUOUS PORTAL FRAME BRACED WALL PANELS SHALL BE CONSTRUCTED IN ACCORDANCE WITH FIGURE R602.10.4.1.1. SEE DETAIL 5/10. SEE IRC2015 SECTION R602.10.4.1.1 AND TABLE R602.10.4.1.1.
  - CRIPPLE STUD WALL FRAMING ABV. PORTAL FRAMES (CONSISTING OF A SINGLE BOTTOM PLATE AND DOUBLE TOP PLATE) MAY BE ADDED AS LONG AS THE COMBINED HEIGHT DOES NOT EXCEED 12' AND THE TWO WALLS ARE STRAPPED TOGETHER ON THE INTERIOR SIDE W/ A VERTICAL 16 GAUGE METAL 1/2" WIDE X 21" LONG STRAP. A MIN. OF 10' OF THE STRAP SHALL BE CONNECTED TO EA. WALL OR GABLE TRUSS W/ 9-16d NAILS FOR A TOTAL OF 18-16d NAILS IN THE ENTIRE STRAP. STRAPS TO BE LOCATED AT EA. END OF THE CONNECTED WALLS OR WALL AND GABLE TRUSS WHERE SPACE ALLOWS FOR THE 10' LENGTH OF STRAP. 4' MAX. ON CENTER STRAP SPACING. THE STRAPS SHALL NOT BE BENT HORIZONTALLY TO ACCOMMODATE WOOD FRAMING. IF APPLICABLE NAILERS SHOULD BE ADDED TO ONE OF THE WALLS OR GABLE END USING A MINIMUM OF 9-16d NAILS TO CREATE THE VERTICAL PLANE NEEDED TO MOUNT THE STRAP.
- EXTERIOR BRACED WALL PANELS SHALL BE CONNECTED TO ROOF FRAMING AS FOLLOWS:
  - PARALLEL RAFTERS OR ROOF TRUSSES SHALL BE ATTACHED TO THE TOP PLATES OF BRACED WALL PANELS IN ACCORDANCE WITH TABLE R602.3(1).
  - WHERE THE DISTANCE BETWEEN THE TOP OF RAFTERS OR ROOF TRUSSES AND PERPENDICULAR TOP PLATES (RAISED HEEL) IS 15-14 INCHES (387 MM) OR LESS, RAFTERS OR ROOF TRUSSES SHALL BE CONNECTED TO THE TOP PLATES OF BRACED WALL PANELS WITH BLOCKING IN ACCORDANCE WITH FIGURE R602.10.6.2(1) AND ATTACHED IN ACCORDANCE WITH TABLE R602.3(1). SEE DETAIL 4/10.
  - WHERE THE DISTANCE BETWEEN THE TOP OF RAFTERS OR ROOF TRUSSES AND PERPENDICULAR TOP PLATES (RAISED HEEL) EXCEEDS 15-14 INCHES (387 MM), PERPENDICULAR RAFTERS OR ROOF TRUSSES SHALL BE CONNECTED TO THE TOP PLATES OF BRACED WALL PANELS IN ACCORDANCE WITH FIGURE R602.10.6.2(3).

BRACED WALL LINE (BWL)	BWL SPACING	STORY LOCATION	METHOD CS-WSP	ADJUSTMENT FACTORS PER TABLE R602.10.3(2)							TOTAL REQ'D	TOTAL PROVIDED	NOTES
				ITEM 1	ITEM 2	ITEM 3	ITEM 4	ITEM 5	ITEM 6	ITEM 7			
BWL-1	20'-0"	2 OF 2	3'-6"	1.00	1.06	0.90	1.45	N/A	N/A	N/A	4'-10"	16'-6"	EAVE TO RIDGE: 11'-2"
BWL-2	33'-0"	2 OF 2	4'-11"	1.00	0.82	0.90	1.45	N/A	N/A	N/A	5'-4"	8'-0"	EAVE TO RIDGE: 7'-0"
BWL-3	20'-0"	2 OF 2	3'-6"	1.00	0.88	0.90	1.45	N/A	N/A	N/A	4'-0"	5'-2"	EAVE TO RIDGE: 8'-0"
BWL-4	33'-0"	2 OF 2	4'-11"	1.00	1.06	0.90	1.45	N/A	N/A	N/A	6'-10"	12'-0"	EAVE TO RIDGE: 11'-2"
BWL-A	39'-0"	2 OF 2	5'-10"	1.00	0.88	0.90	1.45	N/A	N/A	N/A	6'-9"	8'-0"	EAVE TO RIDGE: 8'-0"
BWL-B	35'-0"	2 OF 2	5'-3"	1.00	1.06	0.90	1.45	N/A	N/A	N/A	7'-3"	8'-0"	EAVE TO RIDGE: 11'-2"
BWL-C	39'-0"	2 OF 2	5'-10"	1.00	1.06	0.90	1.45	N/A	N/A	N/A	8'-1"	12'-0"	EAVE TO RIDGE: 11'-2"
BWL-D	35'-0"	2 OF 2	5'-3"	1.00	1.06	0.90	1.45	N/A	N/A	N/A	7'-3"	8'-0"	EAVE TO RIDGE: 11'-0"


BRACED WALL LINE (BWL)	BWL SPACING	STORY LOCATION	METHOD CS-WSP	ADJUSTMENT FACTORS PER TABLE R602.10.3(2)							TOTAL REQ'D	TOTAL PROVIDED	NOTES
				ITEM 1	ITEM 2	ITEM 3	ITEM 4	ITEM 5	ITEM 6	ITEM 7			
BWL-1	24'-8"	1 OF 2	7'-9"	1.00	1.03	1.00	1.30	N/A	N/A	N/A	10'-4 1/2"	24'-0"	EAVE TO RIDGE: 11'-0"
BWL-2	28'-0"	1 OF 2	16'-11"	1.00	1.03	1.00	1.30	N/A	N/A	0.7	15'-10 1/2"	29'-5"	METHOD GB: GB FASTENING: 4" O.C. AT PANEL EDGES, INCLUDING TOP AND BOTTOM PLATES, AND ALL HORIZONTAL JOINTS BLOCKED
BWL-3	28'-0"	1 OF 2	8'-6"	1.00	1.03	1.00	1.30	N/A	N/A	N/A	11'-4 1/2"	18'-0"	
BWL-A	42'-8"	1 OF 2	12'-3"	1.00	1.03	1.00	1.45	N/A	N/A	N/A	18'-3 1/2"	18'-11"	(CS-PF)
BWL-B	32'-8"	1 OF 2	9'-9"	1.00	1.03	1.00	1.45	N/A	N/A	N/A	14'-6 1/2"	15'-0"	
BWL-C	42'-8"	1 OF 2	25'-2"	1.00	1.03	1.00	1.45	N/A	N/A	0.7	26'-3 1/2"	26'-4"	METHOD GB: GB FASTENING: 4" O.C. AT PANEL EDGES, INCLUDING TOP AND BOTTOM PLATES, AND ALL HORIZONTAL JOINTS BLOCKED
BWL-D	26'-8"	1 OF 1	4'-3"	1.00	1.15	1.00	1.45	N/A	N/A	N/A	7'-1"	21'-8"	(CS-PF)

BRACING CALCULATIONS FOOTNOTES:  
CS-PF PANELS CONTRIBUTE 1.5 X ACTUAL LENGTH PER R602.10.3.4  
METHOD GB BWP LENGTH: SINGLE SIDED = 1/2 LENGTH; DOUBLE SIDED = LENGTH



4

SCALE 3/4" = 1'-0"




2

3/4" = 1'-0"




3

3/4" = 1'-0"




1

3/4" = 1'-0"



**FIRST FLOOR BRACING PLAN**



**OVER CONCRETE OR MASONRY FOUNDATION (DETAIL 1 OF 3)**

**METHOD CS-PF: CONTINUOUS  
PORTAL FRAME PANEL CONSTRUCTION**

5

1/2" = 1'-0"

date:

4/23/2025

PERMIT:

7/11/2025

CITY COMMENTS:

8/15/2025

REVISIONS:

9/29/2025

JIM BULEJSKI

ARCHITECTS

315 MARSHALL AVE. SUITE 100 ST. LOUIS, MO 63109

PHONE: 314-662-8700 • FAX: 314-662-8702

E-MAIL: KATE@GBARCHITECT.COM

STATE OF MISSOURI

KATHARINE S. NIESSEN COOK

NUMBER A-2024034183

NEW RESIDENCE AT:

BRACING PLANS & DETAILS

9820 Warington Square

Creve Coeur, MO 63141

sheet:

10

of 11



